



JAIPUR METRO

**JAIPUR METRO RAIL CORPORATION LIMITED**

**General Manager (Civil)**

**(Directorate of Operations & Systems)**

208, 2nd Floor, Admin Building, Depot of JMRC, Bhriugu Path Mansarovar, Jaipur

E-mail-jmrciviloffice215@gmail.com; gmcivil@jaipurmetrorail.in

79/JMRC/OS/Civil/P.way/2023-24/14043

Date: 01/05/2024

**REQUEST FOR QUOTATIONS**

To,

M/s. ....  
.....  
.....

**GST No of the Bidding Firm: -**

**Subject: -Request for Quotation for the Work "Procurement of works related to repair works in RSS building of JMRC, Kiran Path Mansarovar, Jaipur."**

Sealed offers are invited for the Work " Procurement of works related to repair works in RSS building of JMRC, Kiran Path Mansarovar, Jaipur." from the prospective bidders for the subject matter of procurement". Sealed offers should reach the office of General Manager (Civil), O&M- JMRC, 208, 2nd Floor, Admin Building, Depot of JMRC, Bhriugu Path Mansarovar, Jaipur, by 15:00 Hrs. on Date: 08-05-24 Offers received after the due date and time will not be entertained.

Sealed Offers will be opened on due date mentioned above at 15:30 Hrs.

Scope of work is as per Bill of quantity (BOQ) attached as Annexure A.

**Terms and Conditions: -**

1. Firm is required to quote the rates in this format only with Signature and stamp of authorized signatory as a token of acceptance of terms and conditions. The offers submitted in any other format shall be rejected by JMRC.
2. Quoted price for the work shall be inclusive of all extra charges, applicable taxes etc.
3. Order will be given to only one firm, based on gross quoted lowest cost of item to JMRC.
4. Work is to be completed within 30 Days from the Date of Work Order or earlier.
5. Applicable Taxes, Extra Charges etc should be quoted clearly.
6. Offer from the firms who do not have a valid GST No. shall not be entertained. The GST No. Should be clearly indicated in the offer/ bills.
7. Work is required to be done strictly as per item specification as mentioned above.
8. Payment Terms-100% payment after satisfactory completion of work.
9. Inspection authority: Manager Civil
10. Consignee: Jaipur Metro Rail Corporation Ltd.
11. Validity of offer: - Bidder is required to keep their offer open at least 60 days from the date of Bid opening.
12. Bidder name, bid no, Due date & Time should also be mentioned on the sealed offer
13. JMRC reserves the right to accept or reject any offer in whole or part without assigning any reason
14. The offer shall be unconditional and dully signed & Stamped by the Authorized Signatory of Bidding Firm. Conditional offers shall be summarily rejected.
15. The offer will be valid only if the quoted amount by the bidder is less than Rupees 1 lakh.

**Encl.:** Bill of Quantity

Signature & Stamp of Bidder/Contractor

General Manager (Civil)

RajKaj Ref  
6829754



Digitally signed by Karan Singh Meena  
Designation : General Manager  
Date: 2024.04.30 09:56:22 IST





JAIPUR METRO

**JAIPUR METRO RAIL CORPORATION LIMITED**

**General Manager (Civil)**

**(Directorate of Operations & Systems)**

208, 2nd Floor, Admin Building, Depot of JMRC, Bhriku Path Mansarovar, Jaipur

E-mail-jmrcciviloffice215@gmail.com; gmcivil@jaipurmetrorail.in

**Annexure-A**

**BoQ (Bill of Quantity)**

**Name of Work:** "Procurement of works related to repair works in RSS building of JMRC, Kiran Path Mansarovar, Jaipur."

**Rajasthan PWD BSR 2022**

BoQ SL No.	Chapter Code No	Description	Unit	Rate (Rs.)	Quantity	Amount
1	10.21	Providing and laying integral cement based water proofingtreatment including preparation of surface as required fortreatment of roofs, balconies, terraces etc consisting offollowing operations. (a) Applying and grouting a slurry coat of neat cement using2.75 kg/sqm. of cement admixed with proprietary waterproofing compound conforming to IS. 2645 over the RCCslab including cleaning the surface before treatment. (b) Laying cement concrete using broken bricks/brick bats25 mm to 100mm size with 50% of cement mortar 1:4 (1cement : 4 coarse sand) admixed with proprietary waterproofing compound conforming to IS : 2645 over 20 mmthick layer of cement mortar of mix 1:4 (1 cement :4 coarsesand ) admixed with proprietary water proofing compoundconforming to IS : 2645 to required slope and treatingsimilarly the adjoining walls upto 300 mm height includinggrounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat ofcement slurry admixed with proprietary water proofingcompound conforming to IS : 2645. (d) Finishing the surface with 20 mm thick jointless cementmortar of mix 1:4 (1 cement :4 coarse sand) admixed withproprietary water proofing compound conforming to IS :2645 and finally finishing the surface with trowel with neatcement slurry and making of 300x300xmm square (e) The whole terrace so finished shall be flooded withwater for a minimum period of two weeks for curing and forfinal test. All above operations to be done in order and asdirected and specified by the Engineer-in-Charge.With average thickness of 120mm and minimum thickness atkhurra as 65 mm.	Sqm	473.00	27.00	12771
	12.22	Providing and applying white cement based putty over plastered surface to prepare surface even and smooth complete				

Validity unknown Signature valid

Digitally signed by Karan Singh Meena

Designation : General Manager

Date: 2024.04.30 09:56:22 IST

Reason: Approved





JAIPUR METRO

**JAIPUR METRO RAIL CORPORATION LIMITED**

**General Manager (Civil)**

**(Directorate of Operations & Systems)**

208, 2nd Floor, Admin Building, Depot of JMRC, Bhriku Path Mansarovar, Jaipur

E-mail-jmrcciviloffice215@gmail.com; gmcivil@jaipurmetrorail.in

2	12.22.1	New Plastered Surface (three or more coats)	Sqm	84.00	28.00	2352
	12.37	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade including all scaffolding:				
3	12.37.1	New work (two or more coats) over and including scrapping and priming coat with cement primer.	Sqm	75.00	28.00	2100
	12.37.2	Old work (one or more coats) including scrapping surface and necessary repairs.				
4	(b)	Same colour	Sqm	11.00	54.00	594
5	13.29	Repair to damaged RCC slabs, beams and columns etc for strengthening with cement mortar 1 : 2 in following steps :- (i) Choping losse and cracked concrete to required depth, cleaning the exposed surface of steel and concrete with wire brush and sand papering , cleaning of concrete surface with water as necessary and getting dried. (ii) Applying Epoxy primer on the exposed steel bars. (iii) Applying Epoxy hardener and resin mix (as per manufactured's specification) on concrete and steel bars with brush. (iv) Spreading dry cement mortar 1 : 2 mix over epoxy treated wet surface and allow it to dry for one day. (v) Plastering the surface with cement sand mortar 1 : 3 upto depth of 30mm complete. (vi) Cure the plastered surface for 15 days, All work including scaffolding etc. complete in all respect.	Sqm	1568.00	28.00	43904.00
Total Cost of Work (In Figure)						₹61,721.00
Quoted Premium [In Percentge Above/Below (In ±%)]						
Total Quoted Amount (In Fig)						
Total Cost of Work ( In Word ) :						

Validity unknown Signature valid

Signature & Stamp of Bidder/Contractor

RajKaj Ref  
6829754

General Manager (Civil)  
Digitally signed by Karan Singh Meena  
Designation : General Manager  
Date: 2024.04.30 09:56:22 IST