

RAJASTHAN METRO RAIL CORPORATION					ADDENDUM -07	
Name of Work: ICB-2C-03: Design and Construction of Elevated Viaduct and 11 Elevated Stations (including Architectural finishing) viz. B2 Bypass Circle, Durgapura, Gopalpura, Gandhinagar, Nehru Place, Ram Bagh Circle, Narayan Circle, SMS Hospital, Ashok Marg, Government Hostel and Khasa Kothi (Phase-II), Architectural Finishing works of 10 Stations viz. Prahladpura, Manpura, Bilwa Kalan, Bilwa, Goner Mod, Sitapura, JECC, Kumbha Marg, Haldighati Gate and Pinjrapole Gaushala; modification of part operational corridor of Phase-1 and constructing Khasa Kothi (Phase-1) station under Jaipur Metro Phase- II MRTS						
Addendum- 07 Summary Sheet						
S. N.	Section / Part	Document Name	Page No.	Clause No. / Item No.	Addendum / Corrigendum	Remarks
1	PART-II, Section-6 Employer's Requirements	Employer's requirements: Functional	Page No. 12	Clause 2.1.4 NOTES FOR VIADUCT & STATIONS	Subclause 11(xiv) has been modified to clarify the payments to Barricading and Traffic Marshals.	Page no. 12 of Employer's requirements: Functional (Page 435 of Section 6-part 1) has been revised and replaced.

REVISED

within the barricading along the viaduct shall not be more than 9m. Requirements of Safety, Health & Environment as specified in condition of contract on SHE of RMRC.

- (xiv) The contractor shall provide & maintain barricading as per the drawing provided in the bid drawing at the locations where road vehicles / pedestrians are moving, along the Viaduct / Stations / Construction sites as directed by Engineer. The payment of the same is included in lump sum head, shall be made as per the relevant items of Schedule 'B' and the rates of this item includes shifting and maintaining barricading at new location during the currency of the project. Illumination of these barricades/ areas including adjacent road along barricade and Providing suitable number of Traffic marshals to guide the road users and to avoid traffic congestion around the clock as per approved diversion plan & instructions of the engineer is included in the lump sum price.

- (xv) Results of the sub surface investigations conducted at the project site are enclosed with the bid document. The information about the soil and sub soil water conditions is being made available to the contractor in good faith and the contractor is advised to obtain results independently as may be considered necessary by him before quoting rates in the bid. Provisions made in Outline Design Specifications of RMRC will prevail in case of difference in results of two reports. No claims whatsoever on account of any discrepancy between the sub surface conditions that may be actually encountered at the time of execution of work and those given in these bid documents shall be admissible to the contractor under any circumstances.

(xvi) Road Construction / Maintenance / Reinstatement to the original position

- a. Maintaining roads & Footpaths within the barricades **(Viaduct & station area):** -
Maintaining roads, road signage's, central verge, drainage, Footpaths and any other services within the barricade is in the scope of lump sum part of contract till contract period / handing over to the owning agencies. Reinstatement of roads, road signage's, central verge, drainage, Footpaths and any other services to the original shape/ position is also included in lump sum scope of work. Final wearing course of road within barricading area i.e. area affected by construction to be done before handing over to road owning agencies is also included in lump sum price of Schedule 'A'.
- b. Maintenance of roads, road signage's, central verge, drainage, Footpaths and any other services outside the barricaded area: -
Maintenance of road signage's, central verge, drainage, Footpaths and any other services outside the barricaded area for entire road width during contract period / handing over to road owning agencies is in scope of contract. Maintenance of roads outside the barricade area shall be paid under relevant head of BOQ.
- c. Road and footpath outside barricade- Diversion / Widening: -
Construction of road diversion, footpath, widening & laying of drainage lines if required to facilitate traffic movement / diversions as directed by Engineer in Charge. The expenditure incurred for construction of road diversion / widening will be paid to contractor under relevant head of BOQ.
Maintenance of the constructed diversion, footpath during the contract period / up to handing over to road owning agencies shall be responsibility of contractor. Contractor has to maintain diverted road /widened road and footpath free of cost during contract period/ handing over to road owning agencies. No separate maintenance charges will be payable.
Contractor has to maintain a minimum clearance of 5.5 m from road surface to bottom of structure. Any earth work, subgrade work, levelling or other such works for facilitating the movement of the vehicles/ trailers crane positioning etc. is included in the lump sum price.

- (xvii) The construction work shall include loading, unloading and transportation of precast elements and other materials with all lead and lift and erection/launching with cranes/launchers of appropriate capacity.

- (xviii) Any other item of work as may be required to be carried out for completing the construction of elevated structure of specified length including all necessary interfaces works with station and system-wide Contractors in all respects in accordance with the provisions of the Contract and/or to ensure the structural stability and safety during and after construction Works to be performed shall also include all general works, preparatory works of any kind necessary for satisfactory construction, completion and maintenance of the works to the intent and meaning of the drawings adopted and Outline Construction specifications (OCS), to best Engineering standards and orders that may be issued by the Engineer from time to time, compliance by the agency with all Conditions of Contract, supply of all materials, apparatus, plants, equipment, tools, fuel, water, strutting, timbering, transport, offices, stores, workshop, staff, labour and the provision of proper