क्रमांकः एफ १४ () परि/स्टोर/2017—18/नई लिफ्ट/५५५५९ जयपुर, दिनांकः ७५)।०/२०/२

कार्यालय आदेश

परिवहन भवन, मुख्यालय, जयपुर में एक नई लिफ्ट लगाने हेतु निविदाएं आमंत्रित की गई थी । जिनकी निविदा खोलने की निर्धारित दिनाक 29.09.2017 को किसी निविदादाता द्वारा निविदा शुल्क व अमानत राशि जमा नहीं कराने पर निविदाएं खोली नहीं जा सकी।

अतः कार्य की तात्कालिक आवश्यकता को देखते हुए लिफ्ट लगाने हेतु अल्पकालीन निविदा जारी करने की स्वीकृति एतद् द्वारा प्रदान की जाती है।

यह प्रमुख शासन सचिव व आयुक्त, परिवहन विभाग द्वारा अनुमोदित है।

(डॉ. मनीषा अरोड़ा) अतिरिक्त परिवहन आयुक्त (प्रशा.)

प्रतिलिपी:-

- 1. निजी सचिव, प्रमुख शासन सचिव एवं आयुक्त, परिवहन विभाग, राजस्थान।
- 2. कम्प्यूटर शाखा।

अतिरिक्त परिवहन आयुक्त (प्रशा.)

क्रमांकः एफ 14 () परि/स्टोर/2017-18/नई लिफ्ट/ ५५५५५

जयपुर, दिनांकः ०४ /10/2013

अल्पकालीन निविदा सूचना

निम्नलिखित कार्य के लिए केन्द्र एवं राज्य सरकार के अभियांत्रिकी विभागों द्वारा मान्यता प्राप्त एवं अनुभवी संवेदकों से ई—टेन्डरिंग प्रक्रिया से ऑनलाईन निविदाएं आमंत्रित की जाती है:—

क्र. सं.	कार्य का विवरण	लागत (लाखों में)	धरोहर राशि	कार्य पूर्ण करने की अवधि	कार्यालय का नाम एवं पता
	SITC of Passenger elevator in Parivahan Bhawan, Jaipur	15.00	2 प्रतिशत राशि रू. 30000	3 माह	आयुक्त, परिवहन विभाग, सहकार मार्ग, जयपुर

निविदा प्रपत्र को वेब साईट Http://eproc.rajasthan.gov.in से डाउनलोड किया जा सकता है। निविदा से संबंधित जानकारी विभागीय वेबसाईट www.transport.rajasthan.gov.in अथवा RTPP पोर्टल पर भी देखी जा सकती है।

> २०((राजीव कुमार) उप परिवहन ऑयुक्त (यो.वि)

क्रमांकः एफ 14 () परि/स्टोर/2017-18/नई लिफ्ट/44565

जयपुर, दिनांक: ०५/१०/१०/१०/१

अल्पकालीन निविदा सूचना

निम्नलिखित कार्यों के लिए केन्द्र एवं राज्य सरकार के अभियांत्रिकी विभागों द्वारा मान्यता प्राप्त एवं अनुभवी संवेदकों से ई-टेन्डरिंग प्रक्रिया से ऑनलाईन निविदाएं आमंत्रित की जाती है:-

क्र. सं.	कार्य का विवरण	लागत (लाखों में)	कार्य पूर्ण करने की अवधि	जाती है:— कार्यालय का नाम
1.	SITC of Passenger elevator in Parivahan Bhawan, Jaipur	15.00	3 माह	आयुक्त, परिवहन विभाग, जयपुर

निविदा प्रपत्रों को वेब साईट Http://eproc.rajasthan.gov.in से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदकों को निविदा इलेक्ट्रोनिक फॉर्मेट में वेब साईट Http://eproc.rajasthan.gov.in पर online ही भरनी है।

- 1. धरोहर राशि निविदा प्रपत्रों में दर्शाई गई कुल अनुमानित लागत की दो प्रतिशत (बैंक ड्राफ्ट) होगी। फर्म द्वारा धरोहर राशि का डिमान्ड ड्राफ्ट आयुक्त, परिवहन विभाग के नाम जमा कराना
- 2. फर्म का राज्य कर विभाग में पंजीकृत होना अनिवार्य है।
- 3. निविदा केवल पी.एफ लाईसेंस एवं जी एस टी पंजीयन धारक ही भर सकते हैं।
- 4. फर्म को समान प्रकार के एकल कार्य सरकारी अथवा बोर्ड/निगम/ निकाय या अर्द्धसरकारी विभाग में करने का अनुभव प्रमाण पत्र प्रस्तुत करना होगा।
- 5. सभी शर्तें अधिकारिक निविदा प्रपत्र एवं RTPP नियम 2013 के अनुसार मान्य होगी।
- 6. निविदा प्रपत्रों हेतु डाउनलोड की अवधि दिनांक 05.10..2017 को प्रातः 9:00 बजे से दिनांक 15.10.2017 को सायं 6:00 बजे तक होगी।
- 7. (अ)— निविदा प्रपत्र इलेक्ट्रानिक फॉरमेट में वेब साईट http://eproc.rajasthan.gov.in पर दिनांक 16.10.2017 सांयकाल 6:00 बजे तक अपलोड कराए जा सकते हैं एवं प्राप्त निविदाएं इलेक्ट्रानिक फॉरमेट में बेब साईट http://eproc.rajasthan.gov.in पर विभाग द्वारा दिनांक 17.10.2017 को प्रातः 11:00 बजे खोली जाएगी। यदि किसी कारणवश उस दिन अवकाश रहता है तो अगले कार्य दिवस को उसी समय एवं उसी स्थान पर निविदाएं खोली जाएगी।
 - (ब)— निविदा भरने एवं उसके बाद निविदा की समस्त प्रक्रिया ऑन लाईन होगी।

निविदा विभाग की बेबसाईट http://eproc.rajasthan.gov.in पर भी देखी जा सकती है। निविदा प्रपत्र में निविदादाता के लिए योग्यता सूचना, निविदादाता की पात्रता, प्लान, स्पेसिफिकेशन, ड्राईंग विभिन्न कार्यों की मात्रा एवं दरों का विवरण, नियम, शर्ते इत्यादि विवरण वर्णित है।

चैक लिस्ट

अल्पकालीन निविदा सूचना 01/2017–18

1.	कार्य का नाम	
2.	मुख्यालय का नाम	SITC of Passenger elevator in Parivahan Bhawan, Jaipur
3.	अनुमानित लागत	आयुक्त, परिवहन विभाग जगान
4.	धरोहर राशि	15.00 બાલ
5.	निविदा आवेदन /	2% 板. 30,000/—
	डाउनलोड करने की तारीख	05.102017 प्रातः 09.00 बजे से 15.10.2017 सांय 6:00 बजे तक
6.	निविदा जमा/ अपलोड करने की तारीख	16.10.2017 सांय 6:00 बजे तक
7.	निविदा खोलने की तारीख	17.10.2017 प्रातः 11:00 बजे
	निविदा शुल्क एवं धरोहर राशि जमा कराने की तारीख	05.10.2017 से 17.10.2017 प्रातः 10:30 बजे तक आयुक्त, परिवहन विभाग कार्यालय जयपुर।



25

22

me or w	ork : SITC of Passenger Elevator in Parivahan Bhawa	n, jaipur			
	NON BSR ITEM & BSR 2013 Based		<u> </u>		
S.NO	Description	Qty	Unit	Rate	Amount
	BSR ITEMS				
2	Wiring of light point/ fan point/ exhaust fan point/ call				
	bell point with 1.5 sq. mm nominal size FR PVC				
	insulated unsheathed flexible copper conductor 1.1 kV				
	grade and 1.5 sq. mm nominal size FR PVC insulated				
	unsheathed flexible copper earth conductor 1.1 kV				
	grade (IS:694) of approved make in surface /				
	recessed ISI marked medium duty PVC conduit & it's				
	accessories, round tiles,Hot Dipped Galvanized				
	Modular Box with earth terminal, 6 A Modular				
	switch, Modular plate with grid plate, screws, making				
	connections, testing etc. as required. GP1				
	Short point (up to 3 mtr.)	10.00	P. point	260.00	2600
3	Wiring of 3 pin 5 amp. Light plug point with 1.5 sq. mm				
	nominal size FR PVC insulated unsheathed flexible	F1 53 1			
	copper conductor 1.1 kV grade and 1.5 sq. mm				
	nominal size FR PVC insulated unsheathed flexible				
A.	copper earth conductor 1.1 kV grade(IS:694) of				
	approved make in surface / recessed ISI marked				
	medium duty PVC conduit & it's accessories, Hot				
	Dipped Galvanized M.S Modular box of 20 SWG with earth terminal, 6 A modular switch, 6 A modular				
	socket, Modular plate with grid plate, screws, making				
	connections, testing etc. as required.				
	some store, tooling oto: do roquirou.				
	On board	10.00	P. point	244.00	2440.
4	S&F following sizes (dia.) of ISI marked medium duty				
	PVC conduit along with accessories in surface /				ż
	recessed using saddles, clamps, fastener as required				
	including cutting the wall, covering conduit and making				
	good the same as required.Gr I			,	
	25 mm	40.00	R. mtr.	42.00	1680.
5	Supplying and drawing FR PVC insulated &				
	unsheathed flexible copper conductor ISI marked				
	(IS:694) of 1.1 kV grade and approved make in existing surface or recessed conduit/casing capping including	\			
1	making connections etc. as required.Gr I				
	imaking connections etc. as required.or i				-, -
	2 x 2.5 sq. mm. + 1x1.5sqmm	45.00	Mtr.	53.00	2385.
	P&F 240/415 V AC MCB with positive isolation of				0.
	breaking capacity not less than 10 KA (B/ C/ D tripping				12-5
	characteristic) ISI marked IS 8828(1996)]/ conforming				
	to IEC 60898 in existing board/sheets including making connections, testing etc. as required.Gr I				
6					
	Single pole MCB				0
	6 A to 32 A rating	4.00	Each	151.00	604
	Triple pole MCB				0.
	40 A 63 A rating	1.00	Each	1034.00	1034

PM/

S.NO	Description	Qty	Unit	Rate	Amount
* "	P&F Recessed/ Surface mounting heavy duty				
	horizontal type sheet steel Distribution board				
	phophatised/ powder painted complete with suitable				
	rating insulated copper bus bar, shorting link , neutral				
	link, earth link and din bar,masking sheet, conforming				
	to IS13032 & IS8623 including making internal DB				
	terminations with copper lugs , testing etc. as				
7	required.Gr I				
	Double door (single phase)		·		
	12 Way	1.00	Each	1065.00	1065.0
	P&F 240/415 V Residual current circuit breaker				
	conforming to IS:12640:1988/ IEC 61008 on existing				
	board/sheet including making connections, testing etc.				
8	as required GP1				
	Four pole 30 mA sensitivity				
	63 A rating	1.00	Each	2471.0	2471.0
	P/Laying P.V.C. / XLPE insulated & P.V.C. sheathed				
	cable of 1.1 KV grade with aluminium conductor of				
	IS:1554 P-I / IS :7098 P - I of Group 1 of approved				
	make in ground as per IS:1255 including excavation of				
	30cmx75cm size trench, 25 cm thick under layer of				
	sand,IInd class bricks covering, refilling			19-13-1-19	
1	earth, compaction of earth, making necessary				
	connection, testing etc. as required of size.	- 7		*	
9					
	16.0 Sq.mm				
	4 core	40	R. mtr.	178.0	7120
	Maintenance free Gel Earthing with Pipe in pipe /				
	Pipe in strip technology filled with anti corrosive				
	conductive compound (CPRI Tested) below the				
	ground in 150 - 200 mm dia. earth pit & surrounding filled with required mineral filling compound (MFC				
	should have hygroscopic property to retain the				
	moisture for long time to create low resistance zone)				
	and C.C. finished chamber covered with hinged type				
	with locking arrangement C.I. Cover, C.I. Frame of				
	size 300mm x 300mm complete testing of earth				
	resistance as required. of following sizes.				
10					
	With Strip in Pipe Technology with 80 - 100 micron				
- P	GI Coating GI pipe 2000 mm long ,63 / 80mm, Inner strip 50 mm	2	Set		17940
*	x 3 mm copper	2	Set	8970.0	17940
	S & Laying following size earth wire/strip in horizontal			0970.0	
	or vertical run in ground/surface/recess including				
		7			
	Inveling soldenng sandles making connection etc. set				
11	riveting, soldering, saddles, making connection etc. as required				
11	required.	20	Mtr	60	120
11	required. 10 SWG G.I. (Hot Dipped) Wire	20	Mtr.	6.0	120 12200
11	required. 10 SWG G.I. (Hot Dipped) Wire 25mm x 3mm copper strip	25	Mtr.	6.0 488.0	12200
11	required. 10 SWG G.I. (Hot Dipped) Wire 25mm x 3mm copper strip P & F IP-65 protected Wall mounted Bulk Head light				
11	required. 10 SWG G.I. (Hot Dipped) Wire 25mm x 3mm copper strip P & F IP-65 protected Wall mounted Bulk Head light fixture suitable for 15/18 watt CFL lamp with integral	25	Mtr.		12200
11	required. 10 SWG G.I. (Hot Dipped) Wire 25mm x 3mm copper strip P & F IP-65 protected Wall mounted Bulk Head light fixture suitable for 15/18 watt CFL lamp with integral control gear, housing made from cast aluminium with	25	Mtr.		12200
11	required. 10 SWG G.I. (Hot Dipped) Wire 25mm x 3mm copper strip P & F IP-65 protected Wall mounted Bulk Head light fixture suitable for 15/18 watt CFL lamp with integral control gear, housing made from cast aluminium with UV stablized diffuser comprising of copper ballast,	25	Mtr.		12200
11	required. 10 SWG G.I. (Hot Dipped) Wire 25mm x 3mm copper strip P & F IP-65 protected Wall mounted Bulk Head light fixture suitable for 15/18 watt CFL lamp with integral control gear, housing made from cast aluminium with	25	Mtr.		12200

CN.S	Description	Qty	Unit	Rate	Amount
	P & F two pin energy efficient compact fluorscent lamp				1
13	in existing holder/fixture as required. GP1				
	13/18 watt	8	nos.	177.0	1416
	P & F of IP20 LED batten type light fixture made from CRCA				
	sheet steel housing suitable for moutning LED tube system				
	(integral driver), Power Consumption of 18W / 36W 1500-				
	3000 lumens, system lumen efficiency 80 lm/Watt output,				
	life time of 50,000 burning hours with 70% initial lumen				
	maintained. CCT 3000°K, 4000°K & 6000°K GP1				
14					
	4' LED Tube shape fixture 18W	2	nos.	2250.0	4500
				TOTAL	61735

Oned Jerman D.O. Steatpool 27

24/

Nork : SITC of Passenger Elevator in Parivahan Bhawa	n, jaipur			
NON BSR ITEM		_		
Description	Qty	Unit	Rate to be quoted by contractor	Amount
NON BSR ITEM				
STIC of 10 Passenger MRL Elevator with 6 stops, Stainless steel Car, Car door, MS powder coated landing doors, with speed 1.0 MPS, Telescopic doors, VVVF drive controller, ARD and other standard accessories etc. as per Terms & conditions & annexures I to IV specifications attached with 2 year defect liability period. Make OTIS / Kone / Schniedler/Mitsubishi/Thyssen Krupp . After complete installation of elevator , contractor should submit AMC agreement for 2 year DLP period with OEM before final bill .	1	Each		
	NON BSR ITEM SITC of 10 Passenger MRL Elevator with 6 stops, Stainless steel Car, Car door, MS powder coated landing doors, with speed 1.0 MPS, Telescopic doors, VVVF drive controller, ARD and other standard accessories etc. as per Terms & conditions & annexures I to IV specifications attached with 2 year defect liability period. Make OTIS / Kone / Schniedler/Mitsubishi/Thyssen Krupp . After complete installation of elevator , contractor should submit AMC agreement for 2 year DLP period with	NON BSR ITEM NON BSR ITEM SITC of 10 Passenger MRL Elevator with 6 stops, Stainless steel Car, Car door, MS powder coated landing doors, with speed 1.0 MPS, Telescopic doors, VVVF drive controller, ARD and other standard accessories etc. as per Terms & conditions & annexures I to IV specifications attached with 2 year defect liability period. Make OTIS / Kone / Schniedler/Mitsubishi/Thyssen Krupp . After complete installation of elevator , contractor should submit AMC agreement for 2 year DLP period with	NON BSR ITEM NON BSR ITEM SITC of 10 Passenger MRL Elevator with 6 stops, Stainless steel Car, Car door, MS powder coated landing doors, with speed 1.0 MPS, Telescopic doors, VVVF drive controller, ARD and other standard accessories etc. as per Terms & conditions & annexures I to IV specifications attached with 2 year defect liability period. Make OTIS / Kone / Schniedler/Mitsubishi/Thyssen Krupp . After complete installation of elevator , contractor should submit AMC agreement for 2 year DLP period with OEM before final bill	NON BSR ITEM Description Qty Unit Rate to be quoted by contractor NON BSR ITEM SITC of 10 Passenger MRL Elevator with 6 stops, Stainless steel Car, Car door, MS powder coated landing doors, with speed 1.0 MPS, Telescopic doors, VVVF drive controller, ARD and other standard accessories etc. as per Terms & conditions & annexures I to IV specifications attached with 2 year defect liability period. Make OTIS / Kone / Schniedler/Mitsubishi/Thyssen Krupp . After complete installation of elevator , contractor should submit AMC agreement for 2 year DLP period with OEM before final bill



Annexure 1

Name of work SITC of Passenger Elevator in Parivahan Bhawan, Jaipur

1 Type of lift : Gear less & Machine Room Less passenger Elevator

2 Type of Building Office Building (Commercial)

Hoistway Available to be specified as per site

4 Pit Depth 1600 mm

5 Minimum Floor to floor Height 3000 mm

No. of Person

Operation

9

Name of floors to be served

6 Travel Height approx. 18 mtr

10 Passengers to be carried

Ground Plus 5 floors

Selective operation with or without attendant

Speed of Travel 10 1.0Meter/ Sec.

11 Drive Variable voltage variable frequency (V3F) Drive

12 Entrance One at each floor level and same side only.

13 Landing Doors Automatic Centre opening Door panel of Mild Steel in

Powder Caoted finish

Landing door unit integrated on Top floor door frame

Microprocessor based simplex collective full collective

14 Size of car platform : As per required for 10 passengers

15 Door Width As per requirement of 10 passengers elevator.

16 Design of cars body Car Walls in Stainless steel hairline finish

> Car doors in Stainless steel Granite Flooring in Black Sea Standard Deco Ceiling

SS Hand Rail

Mirror on back wall (standerd)

LED / Florescent tube light fitting to have daylight effect inside the

Car light and fan Car cabin. Fan/blower as per manufacturing enriched design.

18 Car position indicator

Floor position indicator at all floors along

with direction of travel indicator.

19 Power supply

Power supply shall be provided as under:

A. 415 volts, 3 phase, 4 wires 50 HzB 230V, Single Phase, 50 Hz for lighting.

C. All electric cables, controls switchgears should be

stricly as per ISI.

20 Standard Features

2 hours Fire rated Landing Doors

Automatic Rescue Device

Overload

Pre - announcing arrows for Collective controls

Position Indicator

Light Curtain protection on Doors

Car and landing operating panel in touch sensitive, stylish, resistant

glass panel

Door open / Close and alarm buttons Visual and acoustic confirmation of call

Call acceptance

Battery Operated alarm bell

Emergency Light Fireman Control Music as usual Auto Car Light off Attendant Operation

21 Specification

IS: 4666. 1968 for electric passenger lifts and shall further

Comply to IS: 1860:1960, IS: 63831,1971, IS

732:1963 and Bombay lift act 1943 amended up to date

a. Electronic door safety (infrared)

b. Automatic rescues device.

Over speed safety system with testing at site facility.

2 years from date of handling over/ date of final bill payment of lifts as per details mentioned in terms & conditions attached herewith.

22 Defect Liability Period

23 Minor Building Work

The lift suppliers include Cost (scope of work of contractor)

- 1 Scaffolding inside the hoist way for erection
- 2 Cutting of walls with repair Including all of bolts members indicator and button boxes etc. in position.
- 3 Sill angles, fascia plates, machine Beams and rolled steel section with bearing plates for support of the nmachine if required.
- 4 Door frames.
- Pit Ladder

29/

24 Sanction and approvals

6. Support chanel work if required at site.
The supplier shall obtain all the sanctions required for the operation of lifts from local authorities if applicable on behalf of the department. The department will reimbursed the actual fees, If any.

25 Tests

The supplier shall test the lift in the presence of lift inspector or department engineer/consultants as per ISI if required.

Signature of contractor

Seal of officer incharge

301917 Verl 201917 Verl 2019 Elev

all

Annexure - II DLP TERMS & CONDITIONS:

- 1. The Defect liability under DLP for 2 years shall be from the date of its completion of the work reckoned by the Engineer-In-charge.
- 2. The defects shall be in case of non-functioning of the following items: Internal and external wiring, panels, cables, LT installation from distribution board to end use points, MCBs, DBs, ELCBs, earthing, switches, sockets, distribution panels, panel switchgears, panel instruments, panel MCBs, bus bars, cable trenching, lugs, connecting wire and any other items specified under the contract.
- Repair and replacement: The items covered under defect liability period shall be replaced and/or repaired as directed by the Engineerin-charge.
- 4. Time period for repair/replacement: The Engineer-in-charge soon after defect arises shall notify to the contracting agency and/or his authorized representative on phone and in writing for rectification of the defect within the prescribed period which may be in hours/days and depends on the gravity and severity of defect.
- 5. Consumable Articles: Consumable Articles like tube rods, CFL, bulbs, HT fuses, batteries, gas filling will be replaced by the client department or user department at their own cost and arrangement.
- 6. Other Items:
 - (a) DG Set including fitting and fixtures.
 - (b) Lifts and Escalators
 - (C) Air Cooling/Air conditioning/Heating System
 - (d) Fire fighting system
 - (e) CCTV, EPABX
 - (f) Security system equipments.
 - (g) Electric Motors pumps
- 7. Conditions regarding Security Deposit:
- (a) Security for DLP:



The contracting agency shall have to furnish security deposit in the form of Bank Guarantee for DLP as per requirements of clause 37 of contract agreement, valid from the date of completion, which shall be assigned by the Engineer-Incharge.

- (b) Forfeiture of Security Deposit:
 In case contracting agency fails to rectify the defects within stipulated period notified to him by the Engineer incharge concerned under contact agreement, the Engineer-incharge shall serve a final notice for 15 days time reckoned from the date of issue of notice to rectify the defects. In case the contracting agency not responding to the notice and fails in rectification of defects the Engineer-incharge will get the defects removed at the risk and cost of the Contracting agency. Action such as encashment of Bank Guarantee and action under enlistment rules etc. shall also be taken against the contracting agency by the competent authority.
- (c) Force Majeure:
 The defects arises due to earthquake, cyclone, and natural calamities shall not be the responsibility of contracting agency.

240

22ml

Seal of officer incharge

Annexuere – III Name of work:- SITC of Passenger Elevator in Parivahan Bhawan, jaipur

IS Codes

The following Bureau of Indian Standards (BIS) shall be followed in Planning, Designing, Installation, Execution & Operations of Elevator System:

S.No	Code No	Year	Description
1	IS: 1860	1980	Code of practice for Installation, Operation & Maintenance of electric passenger & goods elevators.
2	IS: 3534	1976	Outline dimension of electric lifts.
3	IS: 4666	1980	Specification for electric passenger & goods elevators.
4	IS: 2147	1962	Degrees of protection provided by enclosures for low voltage switch gear & control gear.
5	IS: 2148	1981	Flameproof enclosure for electrical apparatus.
6	IS: 557	1979	Guide for selection of electrical equipment For hazardous areas.
7	IS: 5572	1994	Classification of hazardous areas (other than mines) having flammable gases & vapors for electrical installations.

DY

Seal of officer incharge

@ASS

Annexure - IV

Name of work:- SITC of Passenger Elevator in Parivahan Bhawan, jaipur

General Terms and Conditions

	General Terms and Conditions
1	Conditional tenders shall be summarily rejected
2	All materials to be used must be certified in form of packing list and submitted to
	engineer-in-charge before installation as per manufacture manual.
3	Contractor shall be fully responsible for any damage or breakage of civil works in the
	building and contractor shall make good the same without any extra cost
4	The complete elevator installation shall be guaranteed for 24 months from the date of
	nanding over/date of final bill payment i.e. defective liability period during which period
	defective components shall be replaced free of cost, also any leakage current detected
	during this period shall be rectified free of cost.
5	The contractor at his own cost shall arrange all tools and plants required for execution and
	testing of the elevators with satisfaction.
6	Contractor shall submit proof of purchase (voucher/certificate of purchase) of electrical
	items from authorized dealer/distribution/manufacture.
7	Necessary quality control measures and tests shall be carried out at
	site/laboratories/manufacturers premises by the contractor to ensure proper quality
	control.
8	Safe custody of lift items fixed at site shall be the duty of contractor till the work is
	handed over. Space for store will be made at his own level by contractor, . no extra
	payment shall be released by the department for these services.
9	The final payment to the contractor shall be made only after handing over/taking over the
10	work from the clients departments.
10	Bidder should visit the site and inspect the lift well in advance before quoting the rates,
11	No objections shall be entertain after tendering process.
11	After complete installation of elevator, contractor should submit AMC agreement for 2
10	year DLP period with OEM before final bill.
12	Factory inspection of Elevator if required may be carried out by the officer designated
	by the department, contractor shall make necessary arrangement in this regard including
12	advance intimation without any charges.
13	Complete work should be executed as per P.W.D. General Specification for Electrical
1.4	Works (Part-III Lifts & Escalators).
14	Contractor have his own arrangement of electricity/ water supply during installation
	while final testing will be done after clients regular JVVNL connection.

Signature of the Contractor

Ry

Signature of officer in charge